One Building, Start to Finish

What every building at Yosemite Village goes through, in order

01 Notice

Building Work Notice on the door and by email 7 days ahead. Reminder 24 hours ahead. Each notice names the building, the dates and what to move.

RESIDENT ACTION

02 Prep & Protect

Vehicles out of the garage or carport. Shrubs, AC units and patios covered. Limbs over the roof trimmed. Hard-hat zone barricaded.

RESIDENT ACTION

03 Roof Tear-Off & Dry-In

Old roof off to the deck, deck checked and repaired, new insulation and cover board down, dried in the same day. No roof is left open overnight. Garage roofs done in the same visit.

HIGH NOISE

04 TPO Membrane Install

60-mil white TPO, fully adhered, seams heat-welded. Edge metal, flashing, vents and penetrations sealed. Daily magnet sweep.

HIGH NOISE

05 Gutters & Downspouts

Installed once the roof edge is finished. Downspouts discharge away from walks and foundations.

LOW IMPACT

06 Windows

Unit by unit. Where a window needs interior access, the resident books a time slot. Each opening closed the same day.

ACCESS NEEDED

07 Siding

Wall by wall, with house wrap behind it. Wall-mounted items (lights, hose bibs, dishes) removed and reset.

SOME NOISE

08 Paint & HVAC

Trim and body paint to the board's color schedule. Condensers combed or replaced per scope, with a short power-off.

LOW IMPACT

09 Walk, Punch, Sign-Off

Final magnet sweep and cleanup. CCMG walks the building, logs any punch items and closes them before sign-off.

BUILDING CLOSED

Before any roofing: tree trimming pass across the site. Many limbs touch roofs on this property.

Along the west and south fences: debris netting on the neighbor side whenever an edge building is in work.

Weather hold: no tear-off with rain or high wind in the forecast. The schedule shifts, the dry-in rule does not.

Closeout: Yard A turf and any rutted lawn restored, final site sweep, warranty turnover to the board.